

## PRODUCT SPECIFICATION.

Please review all portions of this specification to confirm compliance to site conditions and local building codes.

SECTION 08 8800 General Glazing SECTION – 08 8130 Decorative Glass

## PART 1 – GENERAL

## 1.1 SUMMARY

A. The section includes furnishing and installation of Durascreen Silkscreened & Digitally Printed Glass.

## 1.2 COORDINATION / RELATED SECTIONS

#### A. Related Sections:

- 1. Drawings, General and Supplementary Conditions of the Contract, Division 1 and the following specifications sections apply to this section.
- 2. Section 08 41 00 Entrances and Storefronts
- 3. Section 08 42 00 Entrances
- 4. Section 08 43 00 Storefronts
- 5. Section 08 44 00 Curtainwalls and Glazed Assemblies
- 6. Section 08 50 00 Windows
- 7. Section 08 60 00 Skylights
- B. Section Includes: Glass including, heat-treated glass, insulating glass units, silk-screened glass, spandrel glass and laminated glass.

## 1.3 REFERENCES

- A. ANSI Z97.1 American National Standard for Glazing Materials Used in Buildings –
- B. ASTM C162 Standard Terminology of Glass and Glass Products.
- C. ASTM C1036 Standard Specification for Flat Glass.
- D. ASTM C1048 Standard Specification for Heat-Treated Glass Kind HS, Kind FT Coated and Uncoated Glass.
- E. ASTM C1172 Standard Specification for Laminated Architectural Flat Glass.
- F. ASTM E1300 Standard Practice for Determining the Minimum Thickness and Type of Glass Required to Resist a Specified Load.
- H. ASTM E2188 Standard Test Method for Insulating Glass Unit Performance.
- I. ASTM E2190 Standard Specification for Insulating Glass Unit Performance and Evaluation.
- K. CSPC 16 CFR 1201- Safety Standard for Architectural Glazing Materials.
- L. GANA Glazing Manual: Glass Association of North America.



# architectural products, llc

- M. GANA Sealant Manual: Glass Association of North America.
- N. GANA Laminated Glass Design Guide: Glass Association of North America.

## 1.4 SUBMITTALS

- A. To comply with Section 01330 Submittal Procedures
- B. Product Data: provide produce literature from manufacturer
- C. Engineering Report: Submit Report

# 1.5 DELIVERY, STORAGE and HANDLING

- A. Materials to be delivered to site in manufacture's unopened, crates with labels indicating manufacturer name and product type.
- B. Materials to be stored in a clean and dry indoor location.
- C. Materials to be protected from damage during handling and installation.

## **PART 2 – PRODUCTS**

# 2.1 MANUFACTURER, PRODUCT

A. Paragon Architectural Products, LLC

Phone (480) 767-8266 www.glassengineer.com Fax (480) 767-8267 info@glassengineer.com

B. Durascreen Silk-Screened & Digitally Printed Glass

# 2.2 MATERIALS

- A. Select print method (silk-screened <vector> or digital print <high resolution>)
- B. Glass Material Specify Float Type (standard clear, low-iron, tinted)
- C. Glass Composition
  - 1. Describe glass thickness / layers.
  - 2. Describe inetrlayer formaultion or indicate monolithic glass / non-lamainted glass. If non lamainted indicate surface # where Durascreen print is located.
- D. Visual / Decorative. (Architect to indicate of graphic is vector pattern and high-resolution imagry. Architect to digital drawing of vector graphic or high resolution digital image file)

# **PART 3 - EXECUTION**

# 3.1 EXAMINATION



# architectural products, llc

A. Inspect area to receive glazing panels prior to installation. Notify Architect of any condition that may affect installation or subsequent use. Don't commence installation until proper site conditions exist.

## 3.2 INSTALLATION

- A. Manufacturer to confirm with General Contractor, Subcontractor's qualification. Subcontractor to be responsible for receiving glass products at site and for installation of glazing materials.
- B. Adhere to Structural Support Requirements.
- C. Use silicon adhesive compatible with laminated glass.
- D. Ensure glazing sits on level surface.

# 3.3 CLEANING, PROTECTING

- A. Installer to clean all surfaces of glazing after installation is competed.
- B. Glazing to be protected form damage after installation is complete until date of acceptance by Owner.

**END OF SECTION**